

15-129-10440-0006

To: 1 020032
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- completed 3/9/56
C NE, SEC. 31, T 34 S, R 43 W/E
3960 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4549
Operator: Anadarko Petroleum Corporation
Name & Address: P.O. Box 351
Liberal, KS 67901

Lease Name Interstate Unit Well # 73
County Morton 147.91
Well Total Depth 4551 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1240

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargents Casing Pulling Service License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 12:20 p.m. Day: 22 Month: 9 Year: 19 86

Plugging proposal received from Kirby Lillard

(company name) Sargents Casing Pulling Service (phone) 316-624-7455

were: 5 1/2" at 4550' PBSD 4527' Perfs at 4228-4237

1st plug 4100' with 20 sx cement using tubing. Load hole with lease water. Shoot off casing at freepoint. 2nd plug at casing cut with 30 sx cement

3rd plug at 1300-1100' with 40 sx cement

4th plug at 650-480' 5th plug at 50-0' with 10 sx cement with 35 sx cement

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 7 p.m. Day: 22 Month: 9 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug CIBP at 4100' with 20 sx cement on top, run with tubing

2nd plug at 2020' with 30 sx cement

3rd plug at 1300-1100' with 40 sx cement

4th plug at 650-480' with 35' sx cement
5th plug at 50-0' with 10 sx cement

10-2-86
OCT 2 1986

Remarks: Recovered 2025' 5 1/2" casing. Used common cement by Sargents.
(If additional description is necessary, use BACK of this form.)

INVOICED

(If ~~to~~ observe this plugging.

DATE 10-2-86

Signed Glenn R Barlow (TECHNICIAN)

INV. NO. 15094
9-22