

1060267

129

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- N/A

SE SE , SEC. 30 , T 34 S, R 43 WXX

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5318

Lease Name USA Clinton "F" Well # 1

Operator: Energy Reserves Group, Inc.

County Morton

Name & Address 3613 N.W. 56th, Suite 210

Well Total Depth 4545 147.71 feet

Oklahoma City, OK 73112

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1224

Abandoned Oil Well  Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 3:00 pm Day: 13 Month: July Year: 19 84

Plugging proposal received from Doug Blair

(company name) Sargent's (phone) 316-624-7455

were: 5 1/2 set at 4544' Perfs 3636-86'

RECEIVED  
STATE CORPORATION COMMISSION

1st plug pump 2 sx hulls and 25 sx cement to bottom

JUL 18 1984

2nd plug at 1700' with 30 sx cement

CONSERVATION DIVISION  
Wichita, Kansas

3rd plug at 1270' with 50 sx cement

4th plug at 600' with 30 sx cement

5th plug hulls - plug at 40' Plugging Proposal Received by Paul A. Luthi  
cement to surface with 10 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 5:00 pm Day: 13 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 4544' Perfs 3636' - 86'

1st plug pumped 2 sx hulls and 25 sx cement to bottom, 2nd plug at 1700' with 30 sx cement,  
3rd plug at 1270' with 50 sx cement, 4th plug at 600' with 30 sx cement, 5th & 6th plugs -  
solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

Remarks: They recovered 1721' of 5 1/2" casing. Used Common Sacked cement by Sargent's.  
(If additional description is necessary, use BACK of this form.)

INVOICED

did not observe this plugging.

Signed Paul A. Luthi (TECHNICIAN)

DATE 7-30-84

INV. NO. 2717 7-13