

To: 1 090186
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-23

API NUMBER 15- 025-20,869 - 0000 289

TECHNICIAN'S PLUGGING REPORT
Operator License # 4680
Operator: American Exploration Company
Name & Address 1331 Lamar, Suite 900
Houston, TX 77010-3088

C SE SE, SEC. 8, T. 35 S, R. 25 W/EX
660 feet from S section line
660 feet from E section line
Lease Name Theis "W" Well # 2-8
County Clark 205.56
Well Total Depth 6325 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 794

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor American Exploration Company License Number 4680

Address 1331 Lamar, Suite 900, Houston, TX 77010-3088

Company to plug at: Hour: 4 p.m. Day: 23 Month: 4 Year: 19 92

Plugging proposal received from Gene Allen

(company name) American Exploration Company (phone) 405-752-9036

logs: 4 1/2" at 6325' w/300 sx cement, PBSD 6250', Perfs at 6226-34, 5898-5902, 5924-32'
1st plug set CIBP at 5260' and dump 2 sx cement on top,

2nd plug dump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 5 p.m. Day: 23 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5260' with 2 sx cement on top,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released
8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 550 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by Western. Recovered 2185' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form)

INVOICED
I (operator) do not observe this plugging.

DATE 5-12-92

INV. NO. 35213
4-23

Signed [Signature]
(TECHNICIAN)

STATE CORPORATION COMMISSION
RECEIVED
APR 28 1992
CONSERVATION DIVISION
Wichita, Kansas
FORM CP-2/3
Rev. 01-84