

10-4 15-179-19005-0000

1 020182

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 7/1/53

SW SW NE, SEC. 11, T 31 S, R 32 W X E

2970 feet from S section line

2310 feet from E section line

Lease Name M. Collingwood Well # 1

County Seward 87.69

Well Total Depth 2698 feet

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 643

TECHNICIAN'S PLUGGING REPORT

Operator License # 4742

Operator: Texaco Inc. for Texaco Prod. Inc.

Name & Address P.O. Box 2420

Tulsa, OK 74102

Abandoned Oil Well Gas Well  Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Texaco, Inc. License Number 4742

Address P.O. Box 2420, Tulsa, OK 74102

Company to plug at: Hour: 10:45 a.m. Day: 29 Year: 19 88

Plugging proposal received from Randy Mai

(company name) Texaco, Inc. (phone) 918-560-6000

were: 7 5/8" at 2594' PBTD 2665' Open hole 2594-2698' TOC 900'

Run tubing and pump 50 sx cement at bottom, lay down 3 joints and circulate hole with gel, pull tubing to 1600' and pump 50 sx cement, pull tubing to 600' and pump 50 sx cement, pull tubing to 40' and fill with cement, pump 175-200 sx cement in 10 3/4" X 7 5/8" annulus.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part None

Operations Completed: Hour: 3:30 p.m. Day: 4 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 3 sx hulls and 50 sx cement at 2594', 2nd plug pulled 10 joints tubing and ran 375 sx cement more. Did not circulate cement to surface, water circulated. Fluid level approx. 450-500'. 9/29/88

10/4/88 3rd plug perforated at 690', ran tubing to 1250', pumped 115 sx cement, circulated cement, 4th plug pulled tubing, cement dropped, fluid level at est. 700-750', ran 6 sx hulls mixed with heavy cement, 240 sx cement. Pressured up to 550 psi, shut down, held 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by D. & S. Cementing. No casing recovery.

If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 10-29-88

DIV. NO. 22795

Signed [Signature] (TECHNICIAN)

INVOICED

RECEIVED STATE CORPORATION COMMISSION OCT 13 1988 CONSERVATION DIVISION Wichita, Kansas