

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-20131-00-02  
Spot: SENWNW Sec/Twnshp/Rge: 13-35S-29W  
990 feet from N Section Line, 990 feet from W Section Line  
Lease/Unit Name: ADAMS RANCH Well Number: D-8  
County: MEADE Total Vertical Depth: 6620 feet

Operator License No.: 32581  
Op Name: EXCO RESOURCES, INC.  
Address: 6500 GREENVILLE AVE.-SU 600, LB 17  
DALLAS, TX 75206

Conductor Pipe: Size feet: 8 215.15  
Surface Casing: Size 8.625 feet: 1440 WITH 600 SX CMT  
Production: Size 5.5 feet: 6461 WITH 200 SX CMT  
Liner: Size feet:

Well Type: WSW UIC Docket No: Date/Time to Plug: 01/03/2002 10:00 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CIBP @ 3330' & 2 SX CMT. PLUG AT 1480' WITH 50 SX CMT. PLUG AT 500' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: JIM HOLLAND  
Date/Time Plugging Completed: 01/03/2002 3:30 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: JIM HOLLAND

Actual Plugging Report:

PBTD 4310'. PERFS AT 3388-3404, 3460-70'. SET CIBP @ 3320' WITH 2 SX CMT ON TOP. 1ST PLUG PULL OUT OF HOLE TO 1480'. LOAD HOLE WITH MUD. PUMP 50 SX CMT. GOOD CIRCULATION. DISPLACE WITH MUD. 2ND PLUG PULL OUT OF HOLE WITH 5 1/2" TO 400'. LOAD HOLE & PUMP 40 SX CMT. GOOD CIRCULATION. 3RD PLUG PULL OUT OF HOLE WITH 5 1/2" TO 40'. LOAD HOLE AND PUMP 10 SX CMT TO SURFACE.

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2600' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Jim Holland PART II  
(TECHNICIAN)

RECEIVED  
1-25-02  
JAN 25 2002  
KCC WICHITA

INVOICE U JAN 22 2002  
DATE Jan 25, 02 MP  
INV. NO. 2002061314

Form CP-2/3