

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20488-00-01
Spot: SWSE Sec/Twnshp/Rge: 8-35S-29W
860 feet from S Section Line, 1967 feet from E Section Line
Lease/Unit Name: H G ADAMS III Well Number: 1-8
County: MEADE Total Vertical Depth: 6382 feet

Operator License No.: 32581
Op Name: EXCO RESOURCES, INC.
Address: 6500 GREENVILLE AVE.-SU 600, LB 17
DALLAS, TX 75206

Conductor Pipe: Size feet: 207.42
Surface Casing: Size 8.625 feet: 1502 WITH 750 SX CMT
Production: Size 5.5 feet: 6343 WITH 300 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 12/27/2001 9:45 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CIBP @ 5784' WITH 2 SX CMT. PUMP 50 SX CMT AT 1502'. PUMP 30 SX CMT AT 500'. PUMP 10 SX CMT AT 40'.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 12/27/2001 2:00 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:


PBTD 6307'. PERFS AT 5818-30'. CIBP @ 5784' WITH 2 SX CMT ON TOP. LOAD HOLE WITH MUD. 1ST PLUG AT 1530' WITH 50 SX CMT. 2ND PLUG AT 500' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD. RECOVERED 4020' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED

DEC 31 2001

INVOICED

DEC 27 2001

WICHITA

DATE

01-02-02

INV. NO.

2002061112

Form 10/93

