

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20786-00-00
Spot: SWNWNESE Sec/Twnshp/Rge: 4-35S-29W
2300 feet from S Section Line, 1200 feet from E Section Line
Lease/Unit Name: ADAMS RANCH Well Number: F-35
County: MEADE Total Vertical Depth: 5185 feet

Operator License No.: 32581
Op Name: EXCO RESOURCES, INC.
Address: 6500 GREENVILLE AVE.-SU 600, LB 17
DALLAS, TX 75206

Conductor Pipe: Size 20 feet: 70 8168.57
Surface Casing: Size 8.625 feet: 1537 WITH 715 SX CMT
Production: Size 5.5 feet: 5181 WITH 220 SX CMT
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 12/20/2001 8:55 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 251-1881

Proposed Plugging Method: CIBP @ 4950' & 2 SX CMT. 1ST PLUG AT 1560' WITH 50 SX CMT. 2ND PLUG AT 500' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 12/20/2001 1:30 PM KCC Agent: STEVE MIDDLETON

Actual Plugging Report:

PBTD 5147'. PERFS AT 4992-5012'. CIBP @ 4950' WITH 2 SX CMT ON TOP. LOAD HOLE WITH MUD. 1ST PLUG AT 1565' WITH 50 SX CMT. 2ND PLUG AT 500' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Remarks: USED COMMON CEMENT BY SARGENT & LILLARD. RECOVERED 3230' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED

INVOICED

DEC 31 2001

DATE

01-02-02

DEC 26 2001

KCC WICHITA

JV. NO.

2002061112



Form CP 113

