

1100326

TO: STATE CORPORATION COMMISSION

API NUMBER 15-119-20,217-0001
NE SW NE SW SEC. 9, T 35 S, R 28 W

CONSERVATION DIVISION - PLUGGING SECTION 1650 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1650 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME ADAMS WELL # 1-9

TECHNICIAN'S PLUGGING REPORT

1/24/00

COUNTY MEADE

OPERATOR LICENSE # 32471

WELL TOTAL DEPTH 6700 FEET

217.75

OPERATOR: SUBLETTE OIL COMPANY PRODUCTION CSG: SIZE 4 1/2" @ 5407' WITH 125 SX

NAME AND ADDRESS PO BOX 3726 SURFACE CASING: SIZE 8 5/8" @ 1471' WITH 800 SX

ADDRESS FORT SMITH, AR 72913

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENTS CASING PULLING LICENSE NUMBER 6547

ADDRESS PO BOX 506 LIBERAL, KS 67905-0506

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 24 MONTH: 01 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM KIRBY

(COMPANY NAME) SARGENTS CASING PULLING (PHONE) 316-624-7455

WERE: PERFS AT 5276-5278

1ST PLUG PUMP 100# HULLS AND 20 SX CEMENT AT 5270'. 2ND PLUG SPOT 50 SX CEMENT AT 1500'.

3RD PLUG SPOT 40 SX CEMENT AT 500'. 4TH PLUG SPOT 10 SX CEMENT FROM 40' TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY GARY WITNERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 24 MONTH: 01 YEAR: 2000

ACTUAL PLUGGING REPORT

1ST PLUG PUMP 100# HULLS AND 20 SX CEMENT AT 5270'. 2ND PLUG SPOT 50 SX CEMENT AT 1500'.

3RD PLUG SPOT 40 SX CEMENT AT 500'. 4TH PLUG SPOT 10 SX CEMENT FROM 40' TO SURFACE.

INVOICED

RECEIVED STATE CORPORATION COMMISSION

DATE 2/3/00

FFR - 3 2000

DATE 06/21/00

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 3160' OF 4 1/2" CASING. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Gary Winters (TECHNICIAN) FORM CP-2/3

Handwritten signature and initials