

1 051041

4-20-88
API NUMBER 19-119-20,070-0000 151 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NE, SEC. 7, T 35 S, R 28 W/E
3960 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4215

Lease Name Merkle Well # 1

Operator: American Recovery System Inc.

County Meade 200.40

Name & Address CS Box A0001

Well Total Depth 6166 feet

Oklahoma City, OK 73162

Conductor Pipe: Size feet

(Was Torch Operating)

Surface Casing: Size 8 5/8 feet 1402

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1 p.m. Day: 20 Month: 4 Year: 19 88

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 6115' PBTD 6094' Perfs at 6042-46, 6052-54, 6058-72'

1st plug pump 2 sx hulls and 25 sx common cement to bottom,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release

8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:30 p.m. Day: 20 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx common cement to bottom,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 1000 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by BECA. Recovered 2600' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 4-27-88

INV. NO. 20476

RECEIVED
APR 25 1988
4-25-88
CONSERVATION DIVISION
Wichita, Kansas

Signed Richard W. Luby (TECHNICIAN)