

To: 1 020707
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-21

API NUMBER 15- 119-20,869-0000
NW SE, SEC. 2, T. 35 S, R. 28 W/EX

1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30129

Lease Name Vernon Ross Well # 1-2

Operator: Eagle Creek Corporation

County Meade 107.90

Name & Address 107 N. Market, Ste. 509

Well Total Depth 3320 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1492

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 2 p.m. Day: 20 Month: 9 Year: 19 93

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 3318', TOC 2920', Perfs at 3227-29', PBD 3278'

1st plug pump 100 lbs. hulls and 20 sx cement, displace to 3100',

2nd plug pump 50 sx cement at 1500',

3rd plug pump 35 sx cement at 700',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 3 p.m. Day: 21 Month: 9 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at 3100'

2nd plug pumped 50 sx cement at 1520',

3rd plug pumped 35 sx cement at 650',

4th plug pumped 10 sx cement at 40 to -4'.

All plugs displaced with mud.

Remarks: Used common cement by Sargent's. Recovered 2803' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 10-4-93

INV. NO. 38847

Signed *Steven R. Barlow* (TECHNICIAN)

9-21 DEC 30 1993