

Ro

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Meade County, Sec. 5 Twp. 35S Rge. (E) 28 (W)

Location as "NE/CNW%SW%" or footage from lines Cen. SW NW

Lease Owner Lario Oil & Gas Company

Lease Name LeValley Well No. 1

Office Address 301 S. Market, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 3, 1960

Application for plugging filed October 3, 1960

Application for plugging approved October 3, 1960

Plugging commenced October 3, 1960

Plugging completed October 3, 1960

Reason for abandonment of well or producing formation

Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation Depth to top Bottom Total Depth of Well 6220 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|---------|-------------|
| | | | | 8 5/8 | 1638.80 | Set @ 1650' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with mud to 700'. Plug set at 700' with 25 sacks cement. Mud to 35'. Plug set at 35'. 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

OCT 18 1960

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Service Drilling Company
Address Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Leo Ross (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) X *Leo Ross*
301 South Market, Wichita 2, Kansas
(Address)


SUBSCRIBED AND SWORN TO before me this 12th day of October, 1960

My commission expires July 21, 1962

Frances Leslie
Notary Public.



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas




Company- LARIO OIL & GAS CO.
Farm- LeValley No. 1

SEC. 5 T. 35 R. 28W
C-SW NW

Total Depth. 6223'
Comm. 9-7-60 Comp. 10-2-60
Shot or Treated.
Contractor. Service Drlg. Co.
Issued. 11-19-60

County Meade

KANSAS



Elevation. 2430' KB

Production. Dry

CASING:
13" 32'
3 5/8" 1650' cem w/800 sx.

Figures indicate Bottom of Formations.

| | |
|-------------------------|------|
| sand | 130 |
| sand & red bed | 620 |
| red beds | 955 |
| red beds, shale & anhy. | 1200 |
| red bed & anhydrite | 1470 |
| Anhydrite & shale | 2525 |
| Anhydrite & chalky lime | 2605 |
| lime & shale | 2685 |
| lime, shale & anhydrite | 2750 |
| lime | 2908 |
| lime, shale, chert | 2990 |
| S.L.M. 2990=2953 | |
| sand & lime | 3036 |
| lime & shale | 3110 |
| lime | 3114 |
| lime & shale | 3350 |
| lime | 3432 |
| shale & lime | 3527 |
| lime & shale | 3615 |
| lime, chalk & shale | 3789 |
| lime & shale | 4085 |
| shale | 4530 |
| lime & shale | 4630 |
| lime | 5192 |
| lime & shale | 5293 |
| lime | 5315 |
| shale & lime | 5390 |
| lime | 5472 |
| cherty lime | 5531 |
| lime | 5572 |
| lime & shale | 5782 |
| cherty lime | 5810 |
| lime | 5878 |
| lime & shale | 6000 |
| lime | 6223 |
| Total Depth | |

| | |
|-----------------|------|
| TOPS: | |
| Herington | 2620 |
| Krider | 2658 |
| Winfield | 2695 |
| Upper Ft. Riley | 2750 |
| Lower Ft. Riley | 2816 |
| Florence Flint | 2940 |
| Wreford | 2992 |
| Council Grove | 3048 |
| Heebner | 4472 |
| Toronto | 4520 |
| Lansing | 4641 |
| Marmaton | 5344 |
| Cherokee | 5522 |
| Morrow | 5895 |
| Chester | 6027 |