


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Meade County, Sec. 6 Twp. 35 Rge. 30 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C - NW - NW

Lease Owner B & B Farm Industries
Lease Name Eddy Well No. 1
Office Address Box 638 - Spearman, TX 79081
Character of Well (Completed as Oil, Gas or Dry Hole)



Locate well correctly on above
Section Plat

Gas
Date Well completed April 19 79
Application for plugging filed 6-5-81 19
Application for plugging approved 6-16-81 19
Plugging commenced 6-16-81 19
Plugging completed 6-18-81 19
Reason for abandonment of well or producing formation
Non Commercial Value

If a producing well is abandoned, date of last production
6-14 1981

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Thomas
Producing formation Morrow Depth to top 5580 Bottom 5734 Total Depth of Well 6011
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Council Grove	Gas-Water	2766				
Toronto	Water	4321	4447	8 5/8"	1376'	0
Lansing	Water	4447	5055	4 1/2"	6011	4630
Morrow	Gas	5580	5734			
Miss. Chester	Water	5734	5983			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Pumped 2 sks. hulls & 20 sks. cement to 5450 - Pressured to 750 lbs.
Spotted 50 sks. cement 1350 to 1200
Spotted 25 sks. cement 700' to 625'
Put bridge & 10 sks. cement 40' to 0'
Cut off 8 5/8", 42" below ground level

RECEIVED

STATE CORPORATION COMMISSION

JUN 26 1981

6-26-81

CONSERVATION DIVISION

Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Midwest Casing Pulling Service
Kansas Permit #766

STATE OF KANSAS COUNTY OF HASKELL, ss.
I, Edgar J. Eves (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) Edgar J. Eves
Box F, Sublette, Ks. 67877
(Address)

SUBSCRIBED AND SWORN TO before me this 23 day of June, 1981

Sondra L. Eves
Notary Public.

My commission expires 12-6-84



DRILLERS LOG

EDDY NO. 1


CASING RECORD: OPERATOR: B&B Farm Industries, Inc. DESCRIPTION:
 8-5/8" set @ 1376' CONTRACTOR: Sage Drilling Co., Inc. AP C NW
 w/750 sax cement Sec. 6-35S-30W
 Meade County,
 Kansas
 COMMENCED: March 6, 1979
 TOTAL DEPTH: 6011' COMPLETED: March 19, 1979

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Clay	0	730	
Red Bed	730	1010	
Sand	1010	1185	
Red & Anhydrite	1185	1385	
Shale & Lime	1385	1685	
Shale	1685	2590	
Dolomite	2590	2890	
Shale	2890	3135	
Lime & Shale	3135	3455	
Shale	3455	3945	
Shale & Lime	3945	4190	
Lime & Shale	4190	5100	
Lime	5100	5220	
Lime & Shale	5220	5310	
Shale & Lime	5310	5370	
Lime & Shale	5370	5715	Ran DST#1;
Lime & Shale	5715	5774	
Shale	5774	5847	
Shale & Lime	5847	6011	Logged Hole; 4 1/2" set @ 6011' w/250 sax cement

I certify that this is a true and correct copy of the log on the above captioned well to the best of my knowledge.

SAGE DRILLING CO., INC.

By John R. Bartholomew
John R. Bartholomew



Subscribed and sworn to before me this 23rd day of March, 1979.

Louise K. Whitted
RECEIVED
Louise K. Whitted, Notary Public
STATE CORPORATION COMMISSION

My commission expires:
November 26, 1982

JUN - 9 1981
CONSERVATION DIVISION
Wichita, Kansas