

STATE OF KANSAS
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION
DEC 11 1981
CONSERVATION DIVISION
Wichita, Kansas

Give All Information Complete
Make Required Affidavits
Mail or Deliver Reports to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

WELL PLUGGING RECORD

Meade County, Sec. 6 Twp. 35 Rge. 30 NE/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C NE NE


Lease Owner B & B Farm Industries Inc.
Lease Name Eddy Well No. 2
Office Address Box 638, Spearman, TX 79081
Character of Well (Completed as Oil, Gas or Dry Hole)
Oil

Date Well completed 10-6-80 19
Application for plugging filed 6-22-81 19
Application for plugging approved 7-1-81 19
Plugging commenced 12-3-81 19
Plugging completed 12-5-81 19
Reason for abandonment of well or producing formation
Non Commercial Value

If a producing well is abandoned, date of last production
5-31-81 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Luthi
Producing formation Lansing Depth to top 4315 Bottom 5040 Total Depth of Well 6220'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface				8 5/8"	1457'	0
Production				4 1/2"	4513'	2442'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pumped 1 sks. hulls & 15 sks. cement to 4150' - pressured to 1000 lbs.
Shot off casing @ 2442'
Displaced to 1400' w/mud
Pumped 35 sks. cement 1400' to 1300'
Displaced to 40' w/mud
Put bridge & 10 sks. cement 40' to 0'
Cut off 8 5/8", 3' below ground level

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Midwest Casing Pulling Service
Permit # 766

STATE OF KANSAS COUNTY OF HASKELL, ss.
I, Edgar J. Eves (Employee of Owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Edgar J. Eves
Box F, Sublette, Ks. 67877
(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of December, 19 81

Sandra L. Eves
Notary Public.

My commission expires 12-6-84



DRILLERS LOG

EDDY NO. 2

CASING RECORD: OPERATOR: B & B Farm Industries, Inc. DESCRIPTION:
 8-5/8" set @ 1457' CONTRACTOR: Sage Drilling Co., Inc. C NE NE
 w/700 sax cement COMMENCED: September 18, 1980 Sec. 6-35S-30W
 Meade County,
 Kansas
 TOTAL DEPTH: 6220' COMPLETED: October 6, 1980

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Shale	0	472	
Red Bed	472	1459	
Red Bed & Shale	1459	1740	
Shale & Sand	1740	2218	
Shale	2218	2405	
Lime & Shale	2405	4205	
Shale & Lime	4205	4345	DST #1 @ 4345'
Shale & Lime	4345	4349	DST #2 @ 4349'
Lime & Shale	4349	5360	
Shale & Lime	5360	5450	
Lime & Shale	5450	6013	
Lime	6013	6077	
Shale & Lime	6077	6140	
Lime & Shale	6140	6220	

RECEIVED
 STATE CORPORATION COMMISSION

Logged Hole,
 4 1/2" set @ 4513'
 w/150 sax cement

JUN 23 1981

I certify that this is a true and correct copy of the original on the above captioned well to the best of my knowledge.

SAGE DRILLING CO., INC.

By John R. Bartholomew
 John R. Bartholomew

Subscribed and sworn to before me this 9th day of October, 1980.

Louise K. Whitted
 Louise K. Whitted, Notary Public

