

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-21501-00-01
Spot: NWSE Sec/Twnshp/Rge: 13-31S-35W
1968 feet from S Section Line, 2045 feet from E Section Line
Lease Name: EARL D DAVIS Well #: 1
County: STEVENS Total Vertical Depth: 5850 feet

Operator License No.: 33002
Op Name: KERR-MCGEE OIL & GAS ONSHORE LP
Address: ATTN: FRANK DAVIS P.O. BOX 1330
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4534		WITH 10 SX CMT
PROD	5.5	5845	0	WITH 1425 SX CMT
SURF	8.625	1724		WITH 815 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/03/2015 3:00 PM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 4534' WITH 10 SX CMT. PLUG AT 1774' WITH 50 SX CMT. PLUG AT 550' WITH 60 SX CMT TO 0'.

Plugging Proposal Received By: KEN JEHLIK WitnessType: PARTIAL
Date/Time Plugging Completed: 03/03/2015 5:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 4534' WITH 10 SX CMT. RAN CBL & FOUND TOC @ 1550'. RTIH TO 1784'. 1ST PLUG AT 1784' WITH 40 SX CMT. 2ND PLUG PERFORATE AT 550' WITH 145 SX CMT TO 0'.

Perfs:

Top	Bot	Thru	Comments
5315	5342		
4786	4888		
4584	4778		

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

MAR 25 2015 *CKM*

District: 01

Signed *Kenny Sullivan*
(TECHNICIAN)

RECEIVED
MAR 10 2015
KCC DODGE CITY *MS*

Received
KANSAS CORPORATION COMMISSION

MAR 19 2015
CONSERVATION DIVISION
WICHITA, KS

SA