

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-03883-00-00  
Spot: NESENE Sec/Twnshp/Rge: 15-17S-11W  
1650 feet from N Section Line, 330 feet from E Section Line  
Lease Name: GROSSHARDT Well #: 4  
County: BARTON Total Vertical Depth: 3313 feet

Operator License No.: 33153  
Op Name: KRIER, ROGER DBA KRIER OIL OPERA  
Address: PO BOX 763  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3260		
PROD	5.5	3303		125 SX
SURF	8.625	310		125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/17/2015 8:00 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: ROGER KRIER Company: KRIER OIL Phone: (620) 793-2121

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/18/2015 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1400', 700' and 340'. Ran tubing to 3093' and pumped 12 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1450' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 700' and pumped 185 sx cement w/100 # hulls. Lost circulation on casing. Shut down for the day.  
02/18/2015- Tagged cement at 290'. Ran tubing to 275' and pumped 50 sx cement. Circulated cement to surface. Tied to surface pipe and pumped 30 sx cement. Pushed cement out around surface pipe.  
GPS: 38.57539 -098.51815

Perfs:

Top	Bot	Thru	Comments
3295	3299		
3021	3233		

Remarks: ALLIED CEMENTING CO

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

KCC WICHITA

MAR 18 2015

RECEIVED

MAR 25 2015 *CKM*

FEB 23 2015