

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-203-20231-00-00
Spot: SWSWNENW Sec/Twnshp/Rge: 30-17S-36W
1214 feet from N Section Line, 1426 feet from W Section Line
Lease Name: GERSTBERGER Well #: 1-30
County: WICHITA Total Vertical Depth: 5000 feet

Operator License No.: 6113
Op Name: LANDMARK RESOURCES, INC.
Address: 1616 S VOSS RD STE 600
HOUSTON, TX 77057

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4370		WITH 2 SX CMT
CIBP		4505		
CIBP		4560		
PC		2462		WITH 400 SX CMT
PROD	5.5	4992	0	WITH 150 SX CMT
SURF	8.625	271		WITH 225 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/05/2015 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JASON WALKER Company: LANDMARK RESOURCES Phone: (713) 243-8550

Proposed Plugging Method: CIBP @ 4370' WITH 2 SX CMT. RUN TBG TO 2550' & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 03/06/2015 11:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4370' WITH 2 SX CMT. RAN TBG TO 2567'. PUMP 400 SX CMT. NO CMT TO SURFACE IN 5 1/2" CASING. 3/6/15: TAG TOC @ 420'. FILL 5 1/2" CASING WITH CMT BACK TO 0' WITH 50 SX CMT. ATTEMPT TO PUMP INTO ANNULUS. COULD NOT.

Perfs:

Top	Bot	Thru	Comments
4464	4468		
4429	4433		

Received
KANSAS CORPORATION COMMISSION
MAR 19 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

MAR 25 2015 *CM*

District: 01

RECEIVED
MAR 10 2015
KCC DODGE CITY *MP*

Signed

Ken Jehlik
(TECHNICIAN)

SA