

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-179-21048-00-01  
Spot: S2NENE Sec/Twnshp/Rge: 23-9S-26W  
4290 feet from S Section Line, 660 feet from E Section Line  
Lease Name: PFEIFER Well #: 5  
County: SHERIDAN Total Vertical Depth: 2376 feet

Operator License No.: 8061  
Op Name: OIL PRODUCERS, INC. OF KANSAS  
Address: 1710 WATERFRONT PKWY  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2375		375 SX
SURF	8.625	247		375 SX

Well Type: WSW UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/25/2015 10:00 AM  
Plug Co. License No.: 34141 Plug Co. Name: MOHEGAN WELL SERVICE, LLC  
Proposal Rcvd. from: DAVID HAYES Company: OIL PRODUCERS INC OF KS Phone: (620) 546-4456

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement and 800 # hulls.  
8 5/8" surface casing set at 247' w/160sx cement. 5 1/2" production casing set at 2375' w/350 sx cement. TD 2376'. PBT  
2375'. Perforations: 1223' - 1238' and 2040' - 2070'. CIBP set at 1305'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/25/2015 2:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Pushed CIBP to 2075'. Ran tubing to 2072' and pumped 125 sx cement w/400 # hulls. Pulled tubing to 1104' and pumped 125 sx cement w/400 # hulls. Circulated cement to surface. Pulled tubing to surface. Connected to 8 5/8" surface casing and pumped 20 sx cement. Maximum pressure 400 psi. Connected to 5 1/2" production casing and pumped 20 sx cement.

GPS: 39.25975N -100.18444W

Perfs:

Top	Bot	Thru	Comments
2040	2070		

Remarks: ALLIED CEMENT TICKET # 64,688

Plugged through: TBG

MAR 25 2015  
CKM

District: 04

Signed

Darrel Dipman  
(TECHNICIAN)

Cr

KCC WICHITA

Form CP-2/3

MAR 09 2015

MAR 18 2015

RECEIVED