

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-23845-00-00
Spot: W2SESW Sec/Twnshp/Rge: 23-16S-25W
660 feet from S Section Line, 1650 feet from W Section Line
Lease Name: NUTTLE Well #: 1-23
County: NESS Total Vertical Depth: 4600 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1983		WITH 375 SX CMT
PROD	4.5	4598	0	WITH 150 SX CMT
SURF	8.625	207		WITH 375 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/27/2015 11:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE FRITZLER Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: PUMP DOWN TBG WITH 200# HULLS & 25 SX CMT. PLUG AT 3050' WITH 50 TO 75 SX CMT & 200# HULLS. CIRCULATE AT 1985' CMT TO SURFACE WITH HULLS. USE 50 SX CMT FOR BACKSIDE. CHECK BACKSIDE WITH CMT TO 500 PSI.

Plugging Proposal Received By: ROBERT DICKERSON Witness Type: NONE
Date/Time Plugging Completed: 02/27/2015 1:30 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

RUN TBG TO 4531' WITH 25 SX CMT & 100# HULLS. PULL TBG TO 3050' WITH 50 SX CMT & 200# HULLS. PULL TBG TO 2000' WITH 125 SX CMT & 300# HULLS. CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
4542	4552		

Received
KANSAS CORPORATION COMMISSION
MAR 19 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL.

Plugged through: TBG

MAR 25 2015 *CKM*

District: 01

Signed *Robert Dickerson*
(TECHNICIAN)

5A