

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-195-22447-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 30-14S-21W  
1800 feet from N Section Line, 920 feet from W Section Line  
Lease Name: SCHMIDT 'RP' Well #: 4-30  
County: TREGO Total Vertical Depth: 4054 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 N MARKET STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4059		275 SX
SURF	8.625	214		160 SX
T1	2.375	4024		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/24/2015 10:00 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: WHITETAIL CRUDE Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement, 12 sx gel and 400 # hulls.  
Port Collar at 1496' w/250 sx cement. Perforations: 3959' - 3964'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/24/2015 1:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3950' and pumped 12 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1650' and pumped 130 sx cement. Good circulation of cement. Pulled tubing out. Topped off casing with 15 sx full. Tied on to backside and squeezed with 5 sx full.  
GPS: 38.80780 -099.70433

Perfs:

Top	Bot	Thru	Comments
3959	3964		

Remarks: SWIFT CEMENT TICKET # 26472

Plugged through: TBG

MAR 25 2015 *CM*

District: 04

Signed *Marvin Mills*  
(TECHNICIAN)

CM

FEB 25 2015

KCC WICHITA

Form CP-2/3

MAR 18 2015

RECEIVED