

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-185-21998-00-00  
Spot: NWSWSW Sec/Twnshp/Rge: 24-24S-11W  
1077 feet from S Section Line, 4990 feet from E Section Line  
Lease Name: THOMPSON Well #: 1  
County: STAFFORD Total Vertical Depth: 3900 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3940	2030	WITH 175 SX CMT
SURF	8.625	252		WITH 225 SX CMT

Well Type: SWD UIC Docket No: D23493.0 Date/Time to Plug: 03/10/2015 2:00 PM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: ROBIN AUSTIN Company: RAMA OPERATING Phone: (620) 234-5191

Proposed Plugging Method: SAND BACK TO 3800' WITH 5 SX CMT OR CIBP @ 3800' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/10/2015 2:45 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SANDED BACK TO 3800' WITH 5 SX CMT. 1ST PLUG AT 610' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 50 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
3873	3875		

Received  
KANSAS CORPORATION COMMISSION  
**MAR 19 2015**  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: \*\*COMPLIANCE ISSUE: FAILED MIT\*\* USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

**MAR 25 2015** *AKM*

District: 01

Signed *Robert Dickerson*  
(TECHNICIAN) *JA*

RECEIVED  
**MAR 11 2015** *MP*  
KCC DODGE CITY

Form CP-2/3

cc:UIC