

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-26771-00-00
Spot: NESESWSE Sec/Twnshp/Rge: 18-12S-19W
460 feet from S Section Line, 1370 feet from E Section Line
Lease Name: HAGEN Well #: 1
County: ELLIS Total Vertical Depth: 3930 feet

Operator License No.: 6037
Op Name: STAAB OIL CO., A GENERAL PARTNER
Address: 1607 HOPEWELL RD
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
<u>SURF</u>	<u>8.625</u>	<u>219</u>		<u>150 sx</u>

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 02/24/2015 12:00 AM
Plug Co. License No.: 5655 Plug Co. Name: SHIELDS DRILLING CO., INC.
Proposal Rcvd. from: GEORGE Company: SHIELDS DRILLING CO., INC. Phone: (785) 735-4503

Proposed Plugging Method: Ordered 305 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/24/2015 6:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report: _____ Perfs: _____

1st plug @3832 w/50 sx
2nd plug @1600 w/50 sx
3rd plug @875 w/100 sx
4th plug @270 w/50 sx
5th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Remarks: GLOBAL

Plugged through: DP

MAR 25 2015 KM

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

KCC WICHITA

MAR 18 2015

RECEIVED

Form CP-2/3

MAR 09 2015