

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-101-20224-00-00  
Spot: W2NENE Sec/Twnshp/Rge: 2-17S-29W  
4613 feet from S Section Line, 973 feet from E Section Line  
Lease Name: EATON Well #: 2  
County: LANE Total Vertical Depth: 4608 feet

Operator License No.: 30029  
Op Name: STANDARD OPERATING COMPANY  
Address: 1000 N TYLER STE 100  
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4522		
DVT	5.5	2188		WITH 500 SX CMT
PROD	5.5	4608	0	WITH 250 SX CMT
SURF	8.625	273		WITH 165 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/06/2015 8:00 AM  
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.  
Proposal Rcvd. from: DAVE PAULY Company: STANDARD OPERATING Phone: (316) 721-2020

Proposed Plugging Method: SAND BOTTOM 50' ABOVE PERFS. RUN TBG TO 2200' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/06/2015 10:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED BOTTOM TO 4000' WITH 5 SX CMT. RUN TBG TO 2240' & PUMPED 230 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4529	4534		
4500	4510		
4387	4392		
4272	4282		
4254	4260		
4189	4199		
4132	4136		

Received  
KANSAS CORPORATION COMMISSION  
MAR 12 2015  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

MAR 25 2015 *cm*

District: 01

Signed *Michael Maier*  
(TECHNICIAN)

RECEIVED  
MAR 10 2015 *MP*  
KCC DODGE CITY

*5A*