

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-101-20233-00-00  
Spot: NWSENE Sec/Twnshp/Rge: 2-17S-29W  
3630 feet from S Section Line, 990 feet from E Section Line  
Lease Name: GILLA Well #: 1  
County: LANE Total Vertical Depth: 4600 feet

Operator License No.: 30029  
Op Name: STANDARD OPERATING COMPANY  
Address: 1000 N TYLER STE 100  
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT	5.5	2183		WITH 500 SX CMT
PROD	5.5	4579	0	WITH 250 SX CMT
SURF	8.625	294		WITH 165 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/05/2015 8:00 AM  
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.  
Proposal Rcvd. from: DAVE PAULY Company: STANDARD OPERATING Phone: (316) 721-2020

Proposed Plugging Method: SAND BOTTOM 50' ABOVE PERFS. RUN TBG TO 2200' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/05/2015 11:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED BOTTOM TO 4050' WITH 5 SX CMT. RUN TBG TO 2200' & PUMPED 220 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 300# & HELD.

Perfs:

Top	Bot	Thru	Comments
4526	4536		
4497	4507		
4368	4376		
4315	4319		
4299	4302		
4263	4270		
4250	4255		
4188	4198		
4158	4168		

Received  
KANSAS CORPORATION COMMISSION  
MAR 12 2015  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

MAR 25 2015 *CKM*

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED  
MAR 10 2015  
KCC DODGE CITY

*SA*