

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-20263-00-02
Spot: W2SWNW Sec/Twnshp/Rge: 1-17S-29W
3243 feet from S Section Line, 4924 feet from E Section Line
Lease Name: JAMES C Well #: 2
County: LANE Total Vertical Depth: 4620 feet

Operator License No.: 30029
Op Name: STANDARD OPERATING COMPANY
Address: 1000 N TYLER STE 100
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4055		WITH 3 SX CMT
PROD	5.5	4597	0	WITH 330 SX CMT
SURF	8.625	324		WITH 190 SX CMT

Well Type: EOR UIC Docket No: E19404.4 Date/Time to Plug: 03/06/2015 12:30 PM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: DAVE PAULY Company: STANDARD OPERATING Phone: (785) 798-5051

Proposed Plugging Method: SAND BOTTOM 50' ABOVE PERFS. PERFORATE AT 1250' & PUMP 80 SX CMT OVER CASING VOLUME. IF DOES NOT CIRCULATE PUMP 150 SX CMT DOWN BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/06/2015 12:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

CIBP @ 4055' WITH 3 SX CMT. TIED ONTO CASING & PUMPED 200 SX CMT. MAXIMUM PRESSURE 900#. SHUT IN WITH 250#. TIED ONTO BACKSIDE & PUMPED 150 SX CMT. SHUT IN WITH 100#.

Perfs:

Top	Bot	Thru	Comments
4528	4538		
4501	4505		
4394	4405		
4318	4324		
4254	4256		
4154	4166		
4128	4133		
4120	4124		

Received
KANSAS CORPORATION COMMISSION
MAR 12 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

MAR 25 2015 *cxm*

District: 01

Signed Michael J. Maier
(TECHNICIAN) *SA*

RECEIVED
MAR 10 2015
KCC DODGE CITY *MP*

cc:uic ✓