

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-20266-00-00
Spot: SENE Sec/Twnshp/Rge: 2-17S-29W
4302 feet from S Section Line, 302 feet from E Section Line
Lease Name: EATON Well #: 3
County: LANE Total Vertical Depth: 4594 feet

Operator License No.: 30029
Op Name: STANDARD OPERATING COMPANY
Address: 1000 N TYLER STE 100
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT	5.5	2188		WITH 500 SX CMT
PROD	5.5	4588	0	WITH 250 SX CMT
SURF	8.625	270		WITH 185 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/05/2015 12:00 PM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Rcvd. from: DAVE PAULY Company: STANDARD OPERATING Phone: (316) 721-2020

Proposed Plugging Method: SAND BOTTOM 50' ABOVE PERFS. RUN TBG TO 2200' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/05/2015 1:45 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SANDED BOTTOM TO 4110' WITH 5 SX CMT. RUN TBG TO 2200' & PUMPED 240 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 20 SX CMT. BACKSIDE WAS FULL OF CMT. COULDN'T PUMP IN TO.

Perfs:

Top	Bot	Thru	Comments
4532	4536		
4526	4528		
4338	4342		
4318	4322		
4268	4278		
4254	4260		
4168	4176		

Received
KANSAS CORPORATION COMMISSION
MAR 12 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

MAR 25 2015 *SM*

District: 01

Signed Michael Maier
(TECHNICIAN) *SM*

RECEIVED
MAR 10 2015
KCC DODGE CITY *MR*