

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-05412-00-00
Spot: W2E2SE Sec/Twnshp/Rge: 24-11S-17W
1320 feet from S Section Line, 990 feet from E Section Line
Lease Name: COLAHAN C Well #: 9
County: ELLIS Total Vertical Depth: 3432 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>5030</u>	PROD	7	3428		150 SX
Op Name: <u>VESS OIL CORPORATION</u>	SURF	9.625	1093		300 SX
Address: <u>1700 WATERFRONT PKWY BLDG 500</u> <u>WICHITA, KS 67206</u>					

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/05/2015 9:00 AM
Plug Co. License No.: 32452 Plug Co. Name: SMOKY HILLS WELL SERVICE
Proposal Rcvd. from: JOEL STULL Company: VESS OIL CORP. Phone: (785) 885-8240

Proposed Plugging Method: Ordered 810 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations at 3343' - 3358' simpson, 3362' - 3366' Arb.
Casing leaks at 1167' - 2122'.
ALT 1 Completion

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/05/2015 1:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perforated at 1000'. Smoky Hill Well Service ran in hole with tubing to 3227' and stacked out. Allied rigged to tubing and mixed and pumped 270 sx cement w/300 # hulls mixed in. Pulled tubing to 1643'. Allied rigged to tubing and pumped 375 sx cement w/200 # hulls to circulate cement up 7" casing. Pulled tubing. Rigged to 7" casing with a swedge and pumped 100 sx cement to circulate cement up 9 5/8" casing. Shut in. 9 5/8" and pressured with 7" casing with 200 psi. Shut in pressure 200 psi.

GPS: 39.07841 -099.15211
1343' FSL 980' FEL
SE SW NE SE

Perfs:


Top	Bot	Thru	Comments
3362	3366		
3343	3358		

Remarks: ALLIED CEMENTING CO TICKET # 055644

Plugged through: TBG

MAR 25 2015 *CM*

District: 04

Signed  (TECHNICIAN)
KCC WICHITA

CM

MAR 06 2015

MAR 18 2015

RECEIVED