

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 21 1968
 CONSERVATION DIVISION
 Wichita, Kansas

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Lillard of Cleary Petro. has this

date requested permission to plug the following described well:

Mr. Lillard guarantees payment of the plugging fee.

Operator's full Name: Cleary Petroleum Corporation

Complete Address: 310 Kenmac Bldg., Oklahoma City, Oklahoma

Lease Name: Adams "K" Well No. 1

Location: SE NE Sec. 11 Twp. 35 Rge. 30 (E)(W)

County: Meade Total Depth 6300' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Lillard was instructed to plug the well as follows:

8 5/8" to 2543' circulated w/ cement. ^{5 1/2"} 5122" to 5826' cemented.

3 1/2" liner 5684' to 6299' Top perforations 6254'

Plug bottom w/ 20 sacks cement Top of cement 5550'

Mud 5550' to 1700' Spot 35 sacks cement 1700' to 1600'

Mud 1600' to 40' Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Edmund E. Erbe
 Conservation Division Agent