

State of Kansas



FORM - CP-2

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 12 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Barnard of Pan American Pet. Corp. has this

date requested permission to plug the following described well:

Mr. Barnard guarantees payment of the plugging fee.

Operator's full Name: Pan American Petroleum Corp.

Complete Address: Box 432 Liberal, Kansas

Lease Name: Alexander W. Adams "B" Well No. # 1

Location: SW SW SW Sec. 8 Twp. 35 Rge. 30 (E) (W)

County Meade Total Depth 7921' Oil Well

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Barnard was instructed to plug the well as follows:

13 3/8"-406' Circulated w/cement. 8 5/8"-3475' Cemented. 5 1/2"-7832' Cemented.

Plug bottom 20 Sax. cement top cement 5400' Mud 5400' to 425'

Spotted 125 Sax. cement 425' to 300' Mud 300' to 25'

Plug, 15 Sax. cement 25' to 0

Very truly yours,

Frank Scott  
Conservation Division Agent