

State of Kansas



RECEIVED
CORPORATION COMMISSION

State Corporation Commission

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

DEC - 8 1981

CONSERVATION DIVISION
(Oil, Gas and Water)

CONSERVATION DIVISION
Wichita Kansas

200 Colorado Derby Building
WICHITA, KANSAS 67202

3-December 1981

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. E. Eves of Midwest Casing Pulling
Sublett Kans has this

date requested permission to plug the following described well:

Operator's Full Name: B. B. Farm Industries Inc.

Complete Address: Box F Sublett Kansas 67877

Lease Name: Eddy Well No. 2

Location: C-NE-NE Sec. 6 Twp. 35S Rge. 30W (E) (W)

County: Meade Total Depth: 6220'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Eves was instructed to plug the well as follows:

There is 1457' of 8 5/8" surface casing cement circulated. They run
4510' of 4 1/2" production pipe, and cemented it with 150 lbs of cement
They set a cast iron plug at 4337'. There perforations were from
4318' to 4334' 1st plug at 4337' with 2 lbs of balls + 15 lbs of common
cement pumped to bottom. 2nd plug at 1450' with 35 lbs of common
cement. 3rd plug 40' to 0' on solid bridge with 10 lbs of common
cement. There were 2442' of 4 1/2" production pipe recovered. Midwest
Casing Pulling of Sublett Kans accomplished the plugging.

Very truly yours,
Paul Luster
Conservation Division Agent