

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
SEP 6 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Tracy of Horizon Oil & Gas has this
date requested permission to plug the following described well:

Mr. Tracy guarantees payment of the plugging fee.

Operator's full Name: Horizon Oil & Gas Company

Complete Address: Box 7, Spearman, Texas

Lease Name: Adams "B" Well No. 1-5

Location: C SW NE Sec. 5 Twp. 35 Rge. 30 (E) (W)

County Meade Total Depth 6320' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Tracy was instructed to plug the well as follows:

8 5/8" to 1360' circulated w/ cement. 4 1/2" to 6310' cemented

Top perforations 6120' Plug, bottom w/ 15 sacks cement

Top of cement 5960' Mud 5960' To 700'

Spotted 40 sacks cement 700' to 600' Mud 600' to 40'

Plug, Halls & 10 sacks cement 40' to 0'

Very truly yours,

Edmund A. Evers
Conservation Division Agent