

To: 1 060648
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,78±00-00 R

C SW SW , SEC. 23 , T 34 S, R 32 W/EX

660 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Davies Well # 1-23

Operator: Donald C. Slawson

County Seward 201.50

Name & Address Suite 700, 20 North Broadway

Well Total Depth 6200 feet

Oklahoma City, OK 73102

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8" feet 1558

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 2:00 pm Day: 23 Month: August Year: 19 85

Plugging proposal received from Bab Sargents

(company name) Sargent's (phone) 316-624-7455

were: 4 1/2" at 4778' Perfs at 4522-25' Pump through 4 1/2" with mud between plugs

1st plug set CIBP at 4475'

2nd plug at the chase group with 50 sx cement

3rd plug at 1600' with 50 sx cement

4th plug at 800' with 50 sx cement
solid bridge

5th plug hulls - plug at 40' Plugging Proposal Received by Paul A. Luthi
cement to surface with 10 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:00 pm Day: 23 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4475 and pumped 20' cement on top,

2nd plug at 2600' with 50 sx cement, 3rd plug at 1600' with 50 sx cement, 4th plug at

800' with 50 sx cement, 5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to

surface with 10 sx cement.

Remarks: Recovered 3023' 4 1/2" casing. Used common cement by Sargents

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 28 1985

INV. NO. 9837

8-27

RECEIVED

STATE CORPORATION COMMISSION

AUG 28 1985

CONSERVATION DIVISION

Paul A. Luthi
(TECHNICIAN)

FORM CP-2/3
Rev. 01-84