

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-28340-00-00
Spot: SESENWNW **Sec/Twnshp/Rge:** 36-30S-16E
1280 feet from N Section Line, 4160 feet from E Section Line
Lease Name: CRITERIA **Well #:** SYDNEY#1
County: WILSON **Total Vertical Depth:** 980 feet

Operator License No.: 3830
Op Name: A X & P, INC.
Address: PO BOX 1176
INDEPENDENCE, KS 67301

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	0	0		0 SX
SURF	6.6	20		8 SX

Well Type: DH **UIC Docket No:** **Date/Time to Plug:** 01/26/2015 10:00 AM
Plug Co. License No.: 33969 **Plug Co. Name:** HOUSEL, RICK DBA RICK'S WELL SERVICE
Proposal Rcvd. from: J J HANKE **Company:** A X & P, INC **Phone:** (620) 325-5212

Proposed Plugging Method: Dry Hole. No sand . Circulate heavy gel to surface followed by 10 sx cement. POH to Oswego place 10 sx of cement. POH circulat cement from 250 ft to surface. Top off w. cement.

Plugging Proposal Received By: ALAN DUNNING **WitnessType:** NONE
Date/Time Plugging Completed: 01/26/2015 10:00 AM **KCC Agent:** ALAN DUNNING

Actual Plugging Report:

The drill pipe was hooked onto and circulation established. A 15 sack plug was placed at TD. The drill pipe was pulled to 680 ft and a 15 sack plug was spotted. The drill pipe was pulled to 250 ft and the well to surface with cement. The drill pipe was removed and the well topped off with cement. A total of 72 sacks of portland cement were used to plug well - gel spacers between cement plugs.

Perfs:

RECEIVED
KCC DIST # 3
MAR 30 2015
CHANUTE, KS

AD

Remarks:

Plugged through: OH

4/8/15 CKM

District: 03

Signed Alan Dunning
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 02 2015

CONSERVATION DIVISION
WICHITA, KS