

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-21589-01-00
Spot: SWSWSWE Sec/Twnshp/Rge: 21-31S-18W
163 feet from S Section Line, 2806 feet from W Section Line
Lease Name: JOHN D. WILLBANKS Well #: 1-21H
County: COMANCHE Total Vertical Depth: 5240 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5580		WITH 4 SX CMT
L1	4.5	9740	3427	WITH 525 SX CMT
PROD	7	5590	2355	WITH 150 SX CMT
SURF	9.625	796		WITH 500 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 03/19/2015 8:30 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SET CIBP @ 5580' WITH 4 SX CMT. PLUG AT 1030' WITH 70 SX CMT. PLUG AT 830' WITH 75 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/19/2015 11:50 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 5580' & PUT 4 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LOAD HOLE WITH DRILLING MUD. 1ST PLUG AT 1030' WITH 70 SX CMT. 2ND PLUG AT 830' WITH 75 SX CMT. 3RD PLUG AT 300' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5638	9650		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD. TMD= 9740'.

4/8/15CKM

Plugged through: TBG

Received
KANSAS CORPORATION COMMISSION

District: 01

Signed Steve J. Pfeifer
(TECHNICIAN)

APR 02 2015

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
MAR 25 2015
KCC DODGE CITY