

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-21381-00-00
Spot: NWSWSENE Sec/Twnshp/Rge: 25-14S-33W
2270 feet from N Section Line, 1260 feet from E Section Line
Lease Name: MCGUIRE C Well #: 1
County: LOGAN Total Vertical Depth: 4082 feet

Operator License No.: 34639
Op Name: BLACK TEA OIL, LLC
Address: 1014 E. 29TH ST.
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4079		250 SX
PROD	5.5	4500		230 SX
SURF	8.625	250		180 SX
SURF	8.625	267		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/31/2015 9:30 AM
Plug Co. License No.: 34821 Plug Co. Name: K & M WELL SERVICE INC.
Proposal Rcvd. from: MIKE ATTERBURY Company: BLACK TEA OIL LLC Phone: (316) 990-5919

Proposed Plugging Method: 8 5/8" surface casing set at 267' w/175 sx cement. 5 1/2" production casing set at 4079' w/250 sx cement. Port Collar set at 2155 was not cemented. TD 4082'. Perforations: 3983' - 3990', 3772' - 3782' and 3752' - 3763'. The formation was fractured.

Ordered 100 sx 80/20 pozmix cement, 3% CC, no gel, 400 sx 60/40 pozmix 4% gel, 14 sx gel and 1000 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/31/2015 2:45 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing at 2143' and 1050'. Ran tubing to 3750' and pumped 100 # hulls with water. Pumped 14 sx gel followed by 100 sx 80/20 pozmix 3% cc cement mixed with 500 # hulls. Pulled tubing to 2152' and pumped 110 sx cement w/200 # hulls. Pulled tubing to 1075' and pumped 150 sx cement w/150 # hulls. Circulate with cement. Pulled tubing to surface. Connected to 5 1/2" production casing and pumped 40 sx cement. Casing full. Connected to 8 5/8" surface casing and pumped 100 sx cement w/100 # hulls. Maximum pressure 100 psi. Plug complete.

GPS: 38.80830N -100.93233W

Perfs:

Top	Bot	Thru	Comments
3983	3990		
3772	3782		
3752	3763		

Remarks: GLOBAL CEMENT LLC TICKET # 1633

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

4/8/15 CM

CM

APR 01 2015

Received
KANSAS CORPORATION COMMISSION

APR 06 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3