

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-06737-00-00
Spot: SESESW Sec/Twnshp/Rge: 30-14S-13W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: E MILLER B Well #: 5
County: RUSSELL Total Vertical Depth: 2960 feet

Operator License No.: 34912
Op Name: C12 KANSAS OIL, LLC
Address: 1900 WAZEE ST. SUITE 200
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	15.5	40		
PROD	5.5	2872		100 SX
SURF	6.625	2866		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/23/2015 9:00 AM
Plug Co. License No.: 34946 Plug Co. Name: ACE WELL SERVICE, INC.
Proposal Rcvd. from: AVEN WEAVERLING Company: C12 KANSAS OIL LLC. Phone: (620) 200-1812

Proposed Plugging Method: Ordered 375 sx 60/40 pozmix 4% gel cement

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/23/2015 1:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

03/18/2015- Dug out braden head. 5 1/2" casing had a hole in it. Cut off and replaced 5 1/2" casing 4' down. The area between 6.625" and 5/50" was full of cement below 7' down.
03/23/2015-Perforated at 350', 700' and 1400'. Ran tubing to 2853' and pumped 140 sx cement. Pulled tubing to 1441 and pumped 140 sx cement. Cement circulated to pit. POOH. Hooked to casing and pumped 15 sx cement at 350 psi and shut in.

GPS: 38.79937 -098.81001

Perfs:

Top	Bot	Thru	Comments
2872	2960		
2812	2818		
2608	2648		
2245	2268		

Remarks: QUALITY CEMENTING TICKET # 1099

Plugged through: TBG

4/8/15 CKM

District: 04

Signed Ray A Dinkel (TECHNICIAN) CM

Received
KANSAS CORPORATION COMMISSION

APR 06 2015

CONSERVATION DIVISION
WICHITA, KS

MAR 24 2015

Form CP-2/3