

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-109-20397-00-00
Spot: SWNESW Sec/Twnshp/Rge: 12-12S-34W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: HAYS Well #: 1
County: LOGAN Total Vertical Depth: 4780 feet

Operator License No.: 30104
Op Name: CAMBRON, PAUL L.
Address: 118 N PENN PO BOX 384
NESS CITY, KS 67560

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4780		50 SX
SURF	8.625	367		240 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/24/2015 9:30 AM
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.
Proposal Revd. from: PAUL L CAMBRON Company: PAUL CAMBRON Phone: (785) 798-2282

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.
8 5/8" surface casing set at 367' w/240 sx cement. 4 1/2" production casing set at 4780' w/50 sx cement. Stage collar set at 1750' w/550 sx cement. TD 4780'. Perforations: 4660' - 4668'. Well is non-commercial.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/24/2015 1:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

Perforated production casing at 2660'. Ran tubing to 4597' and pumped 100 sx cement with 200 # hulls. Pulled tubing to 3155' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1598' and pumped 160 sx cement w/200 # hulls. CWC. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 60 sx cement. Casing full. Connected to 8 5/8" surface casing and pumped 30 sx cement. Pressured to 200 psi.

GPS: 39.02240N -101.04876W

Remarks: SWIFT SERVICES TICKET # 27,061

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

4/8/15 CKM

CM

Received
KANSAS CORPORATION COMMISSION

APR 06 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3