

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20274-00-00
Spot: NWSE Sec/Twnshp/Rge: 21-24S-40W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease Name: OVERTON Well #: 2-21
County: HAMILTON Total Vertical Depth: 2450 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, LLC
Address: 6100 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2442	0	WITH 400 SX CMT
SURF	8.625	574		WITH 400 SX CMT

Well Type: GAS UIC Docket No: Date/Time to Plug: 03/10/2015 9:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/10/2015 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 100 SX CMT WITH 150# HULLS VIA 4 1/2" CASING. DISPLACE WITH WATER TO 600'. PRESSURE TO 400#. HOLDING. RAN CBL FROM 600' TO 10'. TOC @ 200'. RUN TBG TO 617' & CIRCULATE CMT TO SURFACE WITH 50 SX CMT. TOOH WITH TBG & TOP OFF WITH 10 SX CMT. PUMP 15 SX CMT DOWN THE ANNULUS TO 200#.

Perfs:

Top	Bot	Thru	Comments
2320	2324		

4/8/15 CKM

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION
APR 02 2015
CONSERVATION DIVISION
WICHITA, KS

RECEIVED
MAR 25 2015
KCC DODGE CITY