

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-00300-00-00
Spot: SESWNE Sec/Twnshp/Rge: 33-21S-14W
2994 feet from S Section Line, 1529 feet from E Section Line
Lease Name: KRAMPE Well #: 1
County: STAFFORD Total Vertical Depth: 3843 feet

Operator License No.: 3553
Op Name: CITATION OIL & GAS CORP.
Address: 14077 CUTTEN RD PO BOX 690688
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3645	0	WITH 100 SX CMT
SURF	8.625	276		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/12/2015 9:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: NEIL PFANNENSTIEL Company: CITATION OIL & GAS Phone: (281) 891-1000

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: NONE
Date/Time Plugging Completed: 03/12/2015 10:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CMT RETAINER AT 3509'. STUNG INTO CMT RETAINER WITH TBG. PUMPED 100 SX CMT THROUGH RETAINER. PERFORATE 5 1/2" CASING AT 870'. RUN TBG IN TO 870'. CIRCULATE CMT UP 8 5/8" X 5 1/2" ANNULUS & FILLED INSIDE OF 5 1/2" CASING WITH 275 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3608	3613		

4/8/15 CKM

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
MAR 25 2015
KCC DODGE CITY

Signed Michael Maier
(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION
APR 02 2015
CONSERVATION DIVISION
WICHITA, KS