

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-171-20829-00-00
Spot: NESENWSW Sec/Twnshp/Rge: 7-19S-34W
1682 feet from S Section Line, 1149 feet from W Section Line
Lease Name: NOVAK Well #: 7-1
County: SCOTT Total Vertical Depth: 4978 feet

Operator License No.: 32384
Op Name: COMANCHE RESOURCES COMPANY
Address: 6520 N WESTERN AVE STE 300
OKLAHOMA CITY, OK 73116

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		2424		CMT TO SURFACE
PROD	5.5	4978	0	WITH 635 SX CMT
SURF	8.625	352		WITH 350 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/19/2015 9:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: MIKE KERNS Company: COMANCHE RESOURCES COMPA Phone: (405) 368-6111

Proposed Plugging Method: SET CIBP @ 4325' WITH 2 SX CMT. PLUG AT 2450' WITH 40 SX CMT. PLUG AT 1340' WITH 40 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/19/2015 12:30 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

SET CIBP @ 4325' WITH 2 SX CMT. 1ST PLUG AT 2450' WITH 40 SX CMT. 2ND PLUG AT 1340' WITH 40 SX CMT. 3RD PLUG AT 400' WITH 50 SX CMT. CMT CIRCULATED. FILLED ANNULUS WITH 15 SX CMT. HELD AT 400#. TOPPED OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4856	4858		
4609	4617		
4376	4388		

4/8/15 CKM

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

Received
KANSAS CORPORATION COMMISSION

APR 02 2015

District: 01

Signed [Signature]
SA (TECHNICIAN)

CONSERVATION DIVISION
WICHITA, KS

RECEIVED
MAR 25 2015
KCC DODGE CITY