

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-01608-00-00
Spot: NESENE Sec/Twnshp/Rge: 9-9S-24W
3676 feet from S Section Line, 419 feet from E Section Line
Lease Name: KEITH Well #: 3
County: GRAHAM Total Vertical Depth: 4000 feet

Operator License No.: 30717
Op Name: DOWNING-NELSON OIL CO INC
Address: PO BOX 1019
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3950		250 SX
SURF	8.625	260		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/23/2015 10:30 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: BRIAN KARLIN Company: DOWNING NELSON OIL CO. INC. Phone: (785) 621-2610

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 11 sx gel and 500 # hulls.
DV Tool at 2418' w/225 sx cement. Production perforations: 3924' - 3928'

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/23/2015 1:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3800' and pumped 11 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 2450' and pumped 150 sx cement w/200 # hulls. Pulled tubing to 1200' and pumped 45 sx cement w/150 # hulls. Pulled all tubing and topped off 5 1/2" casing w/10 sx cement. Hooked to 8 5/8" x 5 1/2" annulus and pumped 5 sx cement. Pressured to 200 psi.

GPS: 39.28693N -099.99710W

Perfs:

Top	Bot	Thru	Comments
3924	3928		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1154

Plugged through: TBG

4/8/15 CKM

District: 04

Signed _____

Pat Bedore
(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAR 24 2015

APR 06 2015

CONSERVATION DIVISION
WICHITA, KS