

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-22902-00-00  
Spot: SWNE Sec/Twnshp/Rge: 31-15S-11W  
4290 feet from S Section Line, 990 feet from E Section Line  
Lease Name: DRISCOLL JOE Well #: 2  
County: RUSSELL Total Vertical Depth: 3385 feet

Operator License No.: 34506  
Op Name: EMPIRE ENERGY E&P, LLC  
Address: 345 RIVERVIEW ST., STE 540  
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3384		160 SX
SURF	8.625	569		250 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/20/2015 11:00 AM  
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD LACEY Company: EMPIRE ENERGY E & P Phone: (620) 617-0603

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 12 sx gel.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/20/2015 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1500', 725' and 570'. Ran tubing to 3200' and pumped 12 sx gel followed by 50 sx cement. Pulled tubing to 1500' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 725'. Circulated cement to surface with 80 sx cement and 100 # hulls.

GPS: 38.64783 -098.78539

Perfs:

Top	Bot	Thru	Comments
3342	3346		
3324	3328		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

4/8/15 CKM

CM

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 06 2015

CONSERVATION DIVISION  
WICHITA, KS