

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-22959-00-01
Spot: NENWNE Sec/Twnshp/Rge: 31-15S-11W
4950 feet from S Section Line, 1650 feet from E Section Line
Lease Name: DRISCOLL JOE Well #: 4
County: RUSSELL Total Vertical Depth: 3342 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 345 RIVERVIEW ST., STE 540
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3337		175 SX
SURF	8.625	597		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/24/2015 8:00 AM
Plug Co. License No.: 30891 Plug Co. Name: LEIKER WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD LACEY Company: EMPIRE ENERGY E & P Phone: (620) 617-0603

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 500 # hulls and 12 sx gel.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/24/2015 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1500', 725' and 600'. Ran tubing to 3264' and pumped 12 sx gel followed by 75 sx cement w/200 # hulls. Pulled tubing to 1525' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 732'. Circulated cement to surface with 60 sx cement and 100 # hulls on casing. Closed casing valve. Circulated cement up surface pipe with 160 sx cement. Pulled tubing. Topped off with 1 sx cement.

GPS: 38.71045 -098.48411

Perfs:

Top	Bot	Thru	Comments
3302	3305		
3292	3294		
3280	3284		
3152	3160		
3132	3136		
3056	3062		
3000	3006		
2972	2976		
2883	2888		
2806	2816		

Remarks: COPELAND ACID AND CEMENTING

Plugged through: TBG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

4/8/15 CKM

CM

Received
KANSAS CORPORATION COMMISSION

MAR 30 2015

APR 06 2015

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS