

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-24577-00-00
Spot: E2E2E2 Sec/Twnshp/Rge: 30-20S-14W
2640 feet from S Section Line, 330 feet from E Section Line
Lease Name: WEATHERS A Well #: 1
County: BARTON Total Vertical Depth: 3730 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3727 | 2296 | 100 SX |
| SURF | 8.625 | 865 | | 425 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/23/2015 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: ROB LONG Company: F G HOLL Phone: (620) 793-0915

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/23/2015 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped with 5 sx cement. Cut casing at 2296'. Pulled casing to 1500' and pumped 125 sx cement w/200 # hulls. Pulled casing to 900' and pumped 50 sx cement w/100 # hulls. Pulled casing to 600' and pumped 50 sx cement w/100 # hulls. Pulled casing to 300'. Circulated cement to surface with 75 sx cement. Pulled casing and hole stayed full.

GPS: 38.28291 -098.80420

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3614 | 3624 | | |

Remarks: QUALITY WELL SERVICE

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

4/8/15 CKM

Received
KANSAS CORPORATION COMMISSION

CM

MAR 30 2015

APR 06 2015

CONSERVATION DIVISION
WICHITA, KS