

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-23199-00-00
Spot: NENENW Sec/Twnshp/Rge: 16-21S-14W
488 feet from N Section Line, 2306 feet from W Section Line
Lease Name: ANSHUTZ A Well #: 1-16
County: STAFFORD Total Vertical Depth: 3820 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3805	2230	WITH 175 SX CMT
SURF	8.625	853		WITH 335 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 03/24/2015 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SQUEEZE PERFS WITH 35 SX CMT & 200# HULLS. PLUG AT 900' WITH 10 SX GEL & 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/24/2015 3:00 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

PUMP DOWN 5 1/2" CASING WITH 200# HULLS & 35 SX CMT. SHUT IN WITH 200 PSI. TAGGED TOC @ 3601'. 1ST PLUG AT 902' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 40 SX CMT. 3RD PLUG AT 42' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
3716	3718		
3678	3682		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10YRS** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

4/8/15 CKM

District: 01

Signed

Robert Dickerson

RECEIVED
MAR 26 2015
KCC DODGE CITY

MD

JA

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

APR 02 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3