

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-023-20597-00-01
Spot: SWNENWNE Sec/Twnshp/Rge: 4-5S-42W
600 feet from N Section Line, 1800 feet from E Section Line
Lease Name: CORDER Well #: 1-4
County: CHEYENNE Total Vertical Depth: 1379 feet

Operator License No.: 30282
Op Name: LOBO PRODUCTION, INC
Address: 2035 RD 68
GOODLAND, KS 67735

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1373		60 SX
SURF	7	115		30 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/19/2015 11:00 AM
Plug Co. License No.: 30282 Plug Co. Name: LOBO PRODUCTION, INC
Proposal Rcvd. from: RICHARD MILLER Company: LOBO PRODUCTION, INC Phone: (785) 899-7277

Proposed Plugging Method: Ordered 127 sx common cement made with 955 gallons of water. Yield 1.50 cubic foot/sx.
7" surface casing set at 115' w/30 sx cement. 4 1/2" production casing set at 1373' w/60 sx cement. TD 1379'. PBT
1372'. Perforations: 1284' - 1294' and 1298' - 1318'.
Well was air drilled.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/19/2015 12:00 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Connected to 4 1/2" production casing and pumped 90 sx cement. Pressured to 300 psi.
Connected to 7" surface casing and pumped 37 sx cement.
GPS: 39.65306N -102.03768W

Perfs:

Top	Bot	Thru	Comments
1298	1318		
1284	1294		

Remarks: SCHLOSSER REDI-MIX TICKET # 11858. COMPANY TOOLS

Plugged through: CSG

4/8/15 CKM

District: 04

Signed Darrel Dipman

(TECHNICIAN)
Received
KANSAS CORPORATION COMMISSION

CM

APR 06 2015

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

MAR 23 2015