

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-023-20598-00-00
Spot: NWSE Sec/Twnshp/Rge: 33-4S-42W
1800 feet from S Section Line, 1900 feet from E Section Line
Lease Name: STROH FARMS Well #: 2-33
County: CHEYENNE Total Vertical Depth: 1396 feet

Operator License No.: 30282
Op Name: LOBO PRODUCTION, INC
Address: 2035 RD 68
GOODLAND, KS 67735

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1390		60 SX
SURF	7	100		26 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/19/2015 11:30 AM
Plug Co. License No.: 30282 Plug Co. Name: LOBO PRODUCTION, INC
Proposal Rcvd. from: RICHARD MILLER Company: LOBO PRODUCTION, INC Phone: (785) 899-7277

Proposed Plugging Method: Ordered 133 sx 60/40 pozmix 4% gel cement with 7.50 gallons of water per sack. Yield 1.50 cubic foot per sack. 7" surface casing set at 100' w/26 sx cement. 4 1/2" production casing set at 1390' w/60 sx cement. TD 1396', PBTD 1385'. Perforations: 1276' - 1296'

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/19/2015 1:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report: _____ Perfs: _____

Connected to 4 1/2" production casing and pumped 82 sx cement. Pressured to 100 psi.
Connected to 7" surface casing with immediate pressure.
GPS: 39.65950N -102.03836W

Remarks: SCHLOSSER REDI-MIX TICKET # 11,962

Plugged through: CSG

4/8/15 CKM

District: 04

Signed Darrel Dipman
(TECHNICIAN) CM

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAR 23 2015

APR 06 2015

CONSERVATION DIVISION
WICHITA, KS