

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-18298-00-02
Spot: SWSESE Sec/Twnshp/Rge: 12-11S-18W
326 feet from S Section Line, 715 feet from E Section Line
Lease Name: HADLEY OWWO Well #: 2 A
County: ELLIS Total Vertical Depth: 3338 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3332		250 SX
SURF	15.5	111		120 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/24/2015 9:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: CRAIG HERTEL Company: MURFIN DRILLING CO., INC. Phone: (785) 623-0123

Proposed Plugging Method: 03/24/2015- Ordered 585 sx 60/40 pozmix 4% gel cement, 13 sx gel and 500 # hulls.
03/25/2015- Ordered 300 sx cement, 400 # hulls and 3 bags CC
PBTD- 3153'
Anchor Catcher and 5 joints of tubing stuck in hole.
Perforations: 2866' - 2870', 2938' - 2942', 3028' - 3032', 3047' - 3050', 3079' - 3089', 3122' - 3126', 3142' - 3145' and 3209' - 3212'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/25/2015 10:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech perforated at 1650', 1132' and 600'. Murfin ran in hole with tubing to 2858'. Quality rigged to tubing and pumped 9 sx gel followed by 100 sx cement w/300 # hulls mixed in. Pulled tubing to 1661'. Quality rigged to tubing and mixed and pumped 285 sx cement w/200 # hulls mixed in. Pulled tubing to 830' and pumped 200 sx cement. Cement did not circulate. Left set overnight.
03/25/2015- Cement at 450' in casing. Murfin ran in hole with tubing to 410'. Quality rigged to tubing and pumped 75 sx cement w/200 # hulls to circulate cement up 7" casing. Pulled tubing. Topped off 7" casing with 10 sx cement. Hole standing full. Rigged to 15 1/2" casing and pumped 20 sx cement to pressure with 200 psi. Shut in pressure 200 psi.
GPS: 39.10398 -099.26128
318' FSL 654' FEL
SW SE SE SE

Perfs:

Top	Bot	Thru	Comments
3209	3212		
3142	3145		
3122	3126		
3079	3089		
3047	3050		
3028	3032		
2938	2942		
2866	2870		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1225 AND 1100

Plugged through: TBG

District: 04

Signed _____

[Signature]
3/26/2015
(TECHNICIAN)

4/8/15 CKM

CM

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 06 2015

CONSERVATION DIVISION
WICHITA, KS