

TO: Revised
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-26489-00-00
Spot: NESWNWSW Sec/Twnshp/Rge: 12-15S-19W
1750 feet from S Section Line, 350 feet from W Section Line
Lease Name: BEFORT Well #: 1-12
County: ELLIS Total Vertical Depth: 3752 feet

Operator License No.: <u>30606</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>MURFIN DRILLING CO., INC.</u>	PROD	5.5	3754		155 SX
Address: <u>250 N WATER STE 300</u> <u>WICHITA, KS 67202</u>	SURF	8.625	223		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/20/2015 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: CRAIG HERTEL Company: MURFIN DRILLING CO., INC. Phone: (785) 623-0123

Proposed Plugging Method: Ordered 285 sx 60/40 pozmix 4% gel cement, 16 sx gel and 500 # hulls.
PC at 1273' w/350 sx cement. 1" on March 22nd 2015 backside with 50 sx cement.
No casing leaks. PBSD: 3731'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/20/2015 9:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Rigged to 5 1/2" casing with a swedge and pumped 50 sx cement w/300 # hulls mixed in followed by 16 sx gel, followed by 160 sx cement w/500 # hulls mixed in to pressure with 1000 psi. Shut in pressure 500 psi.
8 5/8" casing full of cement.
03/26/2015- Operator cut off well and found cement at 150' down. Ellis County Concrete topped off well with 1 yard of cement slurry. Hole full to surface. Ticket # 24896
GPS: 38.75960 -099.39220
1723' FSL 4959' FEL
NE SW NW SW

Perfs:


Top	Bot	Thru	Comments
3653	3659		

Remarks: QUALITY OILWELL CEMENTING TICKET # 1223

Plugged through: CSG

District: 04

Signed



(TECHNICIAN)

4/8/15 CCM
3/26/2015

CM

MAR 26 2015

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 06 2015

CONSERVATION DIVISION
WICHITA, KS