

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-20279-00-00
Spot: SENWSE Sec/Twnshp/Rge: 12-10S-24W
1617 feet from S Section Line, 1643 feet from E Section Line
Lease Name: MANZ Well #: 3
County: GRAHAM Total Vertical Depth: 4245 feet

Operator License No.: 30606

String Size Depth (ft) Pulled (ft) Comments

Op Name: MURFIN DRILLING CO., INC.

PROD 5.5 4059 200 sx

Address: 250 N WATER STE 300
WICHITA, KS 67202

SURF 8.625 200 175 sx

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/12/2013 9:30 AM

Plug Co. License No.: 30606

Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: JOHN GERSTNER

Company: MURFIN DRILLING CO., INC.

Phone: (785) 421-2103

Proposed Plugging Method: Shot perforations at 2450', 2080', 1240' and 195'.
Perforations at 3784' - 3790', 3798' - 3802', 3829' - 3834', 3841' - 3844', 3878' - 3880', 3939' - 3934', 3951' - 3956', 3971' - 3974' and 3992' - 3996'.
Ordered 500 sx 60/40 pozmix 4% gel cement w/800 # hulls.
Tubing broken off at 3787'. Rods and pump are out of the hole.

Plugging Proposal Received By: MARVIN MILLS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 08/12/2013 1:15 PM

KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3741' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 3182' and pumped 255 sx cement w/400 # hulls. Pulled tubing to 2067' and pumped 100 sx cement. Good circulation of cement. Pulled tubing. Tied on to casing and squeezed with 20 sx cement. Casing and backside full.

GPS: 39.19448 -099.94639

Perfs:


Top	Bot	Thru	Comments
3996	4000		
3977	3980		
3960	3963		
3945	3948		

Remarks: SWIFT CEMENT TICKET # 24847

Plugged through: TBG

District: 04

Signed



4/8/15 CKM

MAR 24 2015

MAR 24 2015

Received (TECHNICIAN)
KANSAS CORPORATION COMMISSION

CM

APR 06 2015

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS