

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-065-20244-00-00  
Spot: NWSWSE Sec/Twnshp/Rge: 12-10S-24W  
990 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: GANO SE UNIT Well #: 3-1  
County: GRAHAM Total Vertical Depth: 4245 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N WATER STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4243		200 SX
SURF	8.625	197		175 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/06/2013 12:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Shot perforations at 1910' and 200'.  
Rods and tubing stuck in hole at 1910'. Tried to over shoot and could not get on pipe. Tried to wash down and could not get down.  
Perforations at 3784' - 3790', 3798' - 3802', 3829' - 3834', 3841' - 3844', 3878' - 3880', 3930' - 3934', 3951' - 3956', 3971' - 3974' and 3992' - 3996'.  
Ordered 500 sx 60/40 pozmix 4% gel cement w/800 # hulls.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/06/2013 12:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 1885' and pumped 150 sx cement w/300 # hulls. Let hulls set for 30 minutes and pumped 50 sx cement. Good circulation out of casing. Closed casing valve and had water circulation out the backside. Pumped another 250 sx cement down casing with 200 # hulls. Lost circulation out of the backside and had no more than 300 psi working pressure. Ran out of cement. Tried to pull tubing and it was stuck in the hole. Removed top two joints of tubing. Tied on to backside and pumped 75 sx cement full. Shut in with 600 psi. Tied on to casing and squeezed with 160 sx cement and 500 # hulls full. Shut in with 300 psi.

GPS: 39.19267 -099.94879

Perfs:


Top	Bot	Thru	Comments
3992	3996		
3971	3974		
3951	3956		
3930	3934		
3878	3880		
3841	3844		
3829	3834		
3798	3802		
3784	3790		

Remarks: CONSOLIDATED CEMENT TICKET # 38065

Plugged through: TBG

District: 04

Signed

  
(TECHNICIAN)

CM

Received  
KANSAS CORPORATION COMMISSION

Form CP-2/3

MAR 24 2015

APR 06 2015

CONSERVATION DIVISION  
WICHITA, KS